
VENT PANEL, 2 RU, PERFORATED, 25% OPEN AREA, 12 PC. CONTRACTOR PACK

VTF2-CP12 |



FEATURES & BENEFITS

Contractor Packs provide a cost-effective, space-efficient way for installers to stock the panels they use most frequently. Allows easy access to individual, poly-bagged panels. Designed to stack on warehouse shelving.



- Vented panel with tight perforation to limit visibility
- Flanged steel construction
- Black powder coat finish
- Sold in a contractor pack of 12 pieces
- Pieces are individually poly-bagged, in convenient dispenser box

SPECIFICATIONS

GENERAL INFO

Finish: Black Powder Coat
Quantity: 12

ASSEMBLY/INSTALLATION INFORMATION

Mounting Points: 2

LISTING AGENCIES/THIRD PARTY CERTIFICATIONS

RoHS: Yes
Greenguard: Yes

DIMENSIONS

Panel Width: 19
Height (US): 3.5
Width (US): 19
Rack Units: 2

TECHNICAL INFORMATION

Material: Steel